

2601  
331  
**1997 PRESQUE ISLE COUNTY STATE OF MICHIGAN REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **325** PAGE **080**

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
	<u>Belknap Twp.</u>	<u>H 5</u>
1. Public Land Survey	T <u>34N</u> R <u>5E</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

PRESQUE ISLE COUNTY  
REGISTERED

97 DEC 18 AM 9:55

*Jane M. Lamb*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James A. Beck, in a field survey on Oct. 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5								10					
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

H5 1856 G.L.O. by Alfred Millard  
"Set 1/4 Sec. post"  
Accessories:  
Cedar 8 West 15  
Cedar 6 N10E 7

Date: Oct. 28, 1980 P.A. 74 Recordation ( Land Corner Recordation Certificate Page 514) by Ronald R. Bischer Reg. No 22428  
"Found old Stake Point" 4' East of Single Proportion location set 1/2"  
Rod by old Stake Point"  
N03°W 13.14' 8" Cedar  
S09°E 16.61' 8" Cedar  
S62°W 15.96' 8" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H5 1997 Remonumentation by James A. Beck P.S. 21559  
Found 1/2" iron rod and R.L.S. 15410 ( Delmer Porter) cap

Witnesses found:  
N03°W 13.01 ft., 9" Cedar with root blaze  
S09°E 16.62 ft., 8" Cedar with root blaze  
S62°W 15.61 ft., 8" Cedar with root blaze

**SURVEY & REMONUMENTATION**


**JAN 14 1998**

**SECTION**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H5 1/2" Iron rod and R.L.S. 15410 ( Delmer Porter) cap  
Witnesses:  
N03°W 13.01 ft., 9" Cedar with root blaze  
S09°E 16.62 ft., 8" Cedar with root blaze  
S62°W 15.61 ft., 8" Cedar with root blaze  
S 21°W 16.78 ft., 4" Ash with chest and root blaze

Ratified by Peer Group  
in accordance with P.A. 345  
Chairman Norman J. Quam  
Date 11/13/97



(placed P.S. 21559 caps on all witnesses), Corner falls in swampy area with Cedar, Ash and Birch trees.

Signed by James A. Beck  
Surveyor's Michigan License No. 21559

Date 12/18/1997