

2605

1997 PRESQUE ISLE COUNTY STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 325 PAGE 086

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
	<u>Belknap Twp.</u>	
1. Public Land Survey	T <u>34N</u> R <u>5E</u>	H 13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

PRESQUE ISLE COUNTY
RECORDED
97 DEC 18 AM 9:55
James M. Slamb
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James A. Beck, in a field survey on Oct. 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H 13
1840 G.L.O. by John Hodgson
"Set 1/4 Sec. post"
Beech 8 N71W 21
do(Beech)8 N7 1/2E 27

: Sep. 25, 1978 P.A. 74 (Land Corner Recordation) Certificate, page 261 by Delmer E. Porter Reg. No. 15410
" 1/2" Rod in Mon Box"
Accessories:
N05°E 51.18 Fe. Cor.
N19°E 111.35' 6" Pear; S05°W 35.80' Fe. Cor.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H13 Found 1/2" iron rod and R.L.S. 15410 (Delmer Porter) cap in Monument Box
Accessories found:
S 5°W 35.8 ft. fence corner post

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Norman J. Oran*
Date 11/13/97

SURVEY &
REMONUMENTATION

JAN 14 1998

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H13 Monument:
1/2" iron rod and R.L.S. 15410 (Delmer Porter) cap in Monument Box

Accessories:
S 5°W 35.70 ft. P.S. 21559 tag in fence corner post; N 10°E 43.19 ft., P.S. 21559 tag in 4" Twin Apple
N 67°E 163.05 ft., P.S. 21559 tag in power pole; N 73°E 141.66 ft., 21559 tag in 10" Apple
Corner falls in center of black top roadway East and West at fence line South and brush row North.



Signed by *James A. Beck*
Surveyor's Michigan License No. 21559

Date 12/8/1997