

2615

1997 PRESQUE ISLE COUNTY STATE OF MICHIGAN REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 LIBER **325** PAGE **103**

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
	<u>Belknap Twp.</u>	
1. Public Land Survey	T <u>34</u> N R <u>5E</u>	<u>I 10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

PRESQUE ISLE COUNTY
RECORDED

97 DEC 18 AM 9:56

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SURVEY & REMONUMENTATION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____ **JAN 14 1998**

I, James A. Beck, in a field survey on Oct. 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I 10	1856 G.L.O. by Alfred Millerd	Dec. 21, 1976 P.A. 74 (Land Corner Recordation) Certificate
	" Set qr. Sec. post"	page 167 by Ronald Bischer Reg. No. 22428
	Sugar 8 S60W 13	Part A. No entry
	Sugar 9 N50E 30	Part B. " Set 1/2" iron rod by Single Prop.
		Part C. " 1/2" Rod & Cap
		N 88°W 46.70' Power Pole
		N73°E 20.73' 9"Birch
		N54°W 79.73' 20" Apple Tree

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I 10 Found 1/2" iron rod 1' deep, set 1/2" iron rod and P.S. 21559 cap above


Accessories:
N 88°W 46.77 ft., R.L.S. 15410 (Delmer Porter) tag in power pole
N 73°E 20.58 ft., P.S. 21559 tag in 14" Birch (old tag grown over)

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Norman [Signature]*
Date 11/13/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I 10 1/2" iron rod and P.S. 21559 cap

Accessories:
N 88°W 46.77 ft., R.L.S. 15410 (Delmer Porter) tag in power pole
N 73°E 20.58 ft., P.S. 21559 tag in 14" Birch (old tag grown over)
N 54°W 79.26 ft., P.S. 21559 tag in 22" Apple
S 36°W 63.97 ft., near corner underground cable marker
Corner falls in Easterly (Northbound) side of North-South gravel road.



Signed by *James A. Beck*
Surveyor's Michigan License No. 21559

Date 12/8/1997