

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 325 PAGE 131

For corners in  
Presque Isle  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 34N R 5E      K-5
- T    R
- T    R
- T    R
- 2. Property Controlling    S    T    R
- in Section                S    T    R
- 3. Miscellaneous            S    T    R
- Property in Section    S    T    R

PRESQUE ISLE COUNTY  
RECORDED

97 DEC 22 AM 9:53

*Jenit M. Lantz*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Ronald Bischer, in a field survey on Sept 9, 19 97,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-5

GLO Notes  
Alfred Millerd  
Resurvey 1856  
Black Ash 10" N20° E 31 lks  
Yellow Birch 10 " S65° W 24 lks

1978 Delmer Porter #15410  
Set 5/8" Rod in Mon. Box  
and two witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


K-5

Found 5/8" Rod in Mon Box  
and one Porter witness

SURVEY &  
REMONUMENTATION

JAN 14 1998

SECTION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5

5/8" Rod and cap #22428 in Mon. Box

N70° E 63.51' Power Pole      Porter Witness  
S35° E 57.12' Guard Post  
N36° W 66.42' 12" Elm  
S59° W 96.80' 4" Cedar

Ratified by Peer Group  
in accordance with P.A. 345

Chairman *Norman J. Adams*  
Date 10/30/97

Signed by Ronald R. Bischer

Date Oct. 10, 1997

Surveyor's Michigan License No. 22428