

LIBER 325 PAGE 171

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

97 DEC 23 AM 11:17

For corners in

Presque Isle (County)	Located In:	Corner Code #
1. Public Land Survey	T34NR 5E	M-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Janet M. Lamb
 REGISTER OF DEEDS

SURVEY &
 REMONUMENTATION

JAN 14 1998

SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Delmer E. Porter in a field survey on 11-5, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-2	Set Qr. Sec. Post	Section 1 Survey
GLO Notes	Cedar 15" S65°W 30 Lk	T34N, R5E &
Alfred Millard	Cedar 12" N60°E 20 Lk	Section 6 Survey
July 5, 1856	Old Qr. Cor 6.10 S. &	T34N, R6E, by
		Francis E Spicer
		#7877
		9/29/62

Survey shows no ref. to Cor other than a corner computed position from the 1/8th corners N&S of the 1/4 cor known as M-2, T34N, R5E and A-2, T34N, R6E
 Survey was done for MI Limestone Corporation

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2	1/2" Rod & 4"X4" Post
Nov. 5, 1997	N88°W 6.65' 6" Basswood
Survey by	N59°W 18.43' 8" Cedar
Porter's Survey	N45°E 2.40' 12" Aspen
using Spicer Notes	N51°E 13.87' 12" Balsam
Found 1/2" Rod	Placed Cap #33984 on Rod
& 4"X4" Post	



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2	1/2" Rod & Cap #33984 & 4"X4" Post
	N88°W 6.65' 6" Basswood
	N59°W 18.43' 8" Cedar
	N45°E 2.40' 12" Aspen
	N51°E 13.87' 12" Balsam

Ratified by Peer Group
 In accordance with P.A. 345
 Chairman *Norman J. Quinn*
 Date 12/4/97

Signed by *Delmer E. Porter*
 Surveyor's Michigan License No. 15410

Date 12/18/97