

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 35. NR. 4. E. --  
T 36 NR 4 E

----- Presque Isle ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 1-2-35-36

DESCRIPTION OF CORNER MONUMENT 1/2"x14" iron bar and rocks  
-----

WITNESSES TO CORNER -----

8" Maple - N45W - 1 links

9" Maple - S9W - 25 links

\*7" Maple - S87E - 33 links

-----  
\* Squared 4 sides 18 years ago.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. Corner was set by proportionate measurement between town corner east and corner to Sections 2 and 3 west. Could not identify anything for government BTs. This point makes the mile north somewhat short, but compares with the east line of Section 36. Corner is about 60 links west of trail from north, and 33 links west of a Maple that was blazed on 4 sides about 18 years ago, and was probably considered as the approximate corner.

Corner was placed and witnessed May 25, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 6/3/59 -  
REGISTERED LAND SURVEYOR