

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35.. NR. 4 E. ---
T 36 NR 4 E

Presque Isle COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 2-3-34-35

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

5" Balsam	-	S68E	-	54 links
5" Balsam	-	S47W	-	111 links
4" Balsam	-	N10E	-	15½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this area. Found a very old scribed post at corner, possibly 30-40 years old, set by unknown, but similar to others located in this area. Probable government BT NE is down and burned, and a possible site NW. Can locate nothing else in vicinity to contradict this as the best available evidence of the corner.

Corner was placed and witnessed May 25, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*
REGISTERED LAND SURVEYOR

DATE 6/3/59