

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35. NR. 4 E.

T 36 NR 4 E

Presque Isle COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 4-5-32-33

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

9" Cedar	-	N36W	-	20 links
7" Cedar	-	South	-	14½ links
7" Cedar	-	S87E	-	45½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this area. Corner was restored from three gov't BTs. The SE and NE gov't Cedar stumps in place with marks, and the NW W. Pine with notch. Corner falls at south edge of an old logging trail E-W, and was set to perpetuate a government corner and to control surveys in other sections.

Corner was placed and witnessed May 26, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 6/3/59
REGISTERED LAND SURVEYOR