

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 35 N.R. 4 E
T. 36 NR 4 E
Presque Isle COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 2 and 35

CORNER MONUMENT 1" pipe with 4" brass cap, below surface

DATE MONUMENT PLACED AND WITNESSED February 22, 1961

WITNESSES TO CORNER.....



6" Maple	-	S67W	-	34.5 feet
8" Maple	-	S40E	-	25.0 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement, midpoint on line between section corners, by Forestry Division survey crew while making a survey in this area. Unable to identify anything for government BTs. Corner falls in center of meandering E-W trail road.

SURVEYOR'S SEAL

SIGNED *Kenneth Ostling* DATE 2-24-61
REGISTERED LAND SURVEYOR