

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 35 N. R. 4 E.	B-11, C-11, D-13
2. PROPERTY CONTROLLING IN SECTION 31	T. 35 N. R. 4 E.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 1, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-11 Found pipe at corner as previously restored from U.S. B.T. stamp which is still in place.
- C-11 Set corner by reference to 1/8 and 1/4 corner West and other physical features. Falls nearly in line with old fence West and South.
- D-13 Set corner in fences corner N-S & E. Found remains of stake at corner when setting monument. Adjacent owner in Sec. 5 claims to have had survey of his ownership in 1944

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11	C-11	D-13
Left 1½" pipe in place	Set DNR Monument	Set DNR Monument
U.S. B.T. R. Pine Stp. N33°W 13.20'	12" Cedar S48°W 29.2'	4" R. Pine N76°W 20.1
6" Cedar S58°E 13.3'	14" Cedar N58°W 6.0'	4" R. Pine S28°W 25.2
3" Cedar S02°E 18.2'		

SIGNED BY Kenneth Ostling DATE 9/4/80

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

