

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>35</u> ^{N.} 36 R. <u>5</u> ^{E.} W.	M.C. #15 between Sec. 15&16
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ ^{N.} S., R. _____ ^{E.} W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S., R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, D. L. Bisell do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 13, 1971, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

N 10^W, True line between Sections 15 & 16
47.00 chains - intersected Lake Huron and set meander post.
Y. Pine 6, S 20^E, 127 links
Y. Pine 8, S 89⁰ 30'W, 96 links

May 19, 1856

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

SW corner Section 15 found; W 1/4 corner, Section 15 found as recorded @ 2639.91 (vs. 2640 G.L.O.) Various city plats tied to these corners. G.L.O. notes were traced in re-establishment of meander corner. A search revealed no evidence of the monument or of its accessories, except its relationship to Lake Huron.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Meander Corner #15
Set 1" pipe with standard cap.
N 87⁰W, 14.60, 10" spruce, spike and tag.
S 37⁰W, 63.34, 7" spruce, spike and tag, 4' high.

SIGNED BY Donald L. Bisell DATE 11-17-71

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bisell ^{CHIEF OF SURVEY PARTY} _{MICHIGAN REGISTERED LAND SURVEYOR} DATE 11-17-71 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655