

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
PRESQUE ISLE
(County)

Located in: Corner Code #/

- | | | |
|------------------------------------|--------------------------|-------|
| 1. Public Land Survey | T <u>36N</u> R <u>2E</u> | G8 ✓ |
| | T <u>36N</u> R <u>2E</u> | G9 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

PRESQUE ISLE COUNTY
 RECORDED

2000 DEC 11 AM 9:46

Janet M. Jambo
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	14	15	16	17	18	19	20	21	22	23	24	25	26
4	27	28	29	30	31	32	33	34	35	36	37	38	39
5	40	41	42	43	44	45	46	47	48	49	50	51	52
6	53	54	55	56	57	58	59	60	61	62	63	64	65
7	66	67	68	69	70	71	72	73	74	75	76	77	78
8	79	80	81	82	83	84	85	86	87	88	89	90	91
9	92	93	94	95	96	97	98	99	100	101	102	103	104
10	105	106	107	108	109	110	111	112	113	114	115	116	117
11	118	119	120	121	122	123	124	125	126	127	128	129	130
12	131	132	133	134	135	136	137	138	139	140	141	142	143
13	144	145	146	147	148	149	150	151	152	153	154	155	156

I, James A. Beck, in a field survey on OCTOBER 25, 2000 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | |
|----|--------------------------------------------------------------------------------|----|-------------------------------------------------------------------|
| G8 | January 19, 1981 PA 74 (Land Corner Recordation) Certificate by Ronald Blacher | G9 | October 28, 1997 P.A. 74 Certificate by Ronald Blacher P.S. 22428 |
| | A. "Pipe by Delimeter Record on File" | | 1" pipe and 2 old witnesses |
| | B. "Found 3/4" Pipe at Fs. Corner" | | N85°E 2.68' 9" Maple, old witness |
| | C. 3/4" Pipe | | S47°W 30.47' 9" Maple, old witness |
| | N11degW 48.42' 5" Ironwood | | N08°W 11.09' 9" Maple |
| | N49deg W 28.68' 12" Maple | | S14°E 13.29' 8" Maple |
| | S43degW 31.95' 6" Aspen | | |

SURVEY &
 REMONUMENTATION

FEB 12 2001

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | | | |
|----|------------------------------------------------------------|----|-------------------------------------------|
| G8 | Found 3/4" pipe at very old fence corner post | G9 | found 1" pipe, set P.S. 21559 cap in pipe |
| | N11°W 48.42' RLS 15410 tag in 7" Ironwood in group of four | | Witnesses: |
| | N49°W 28.68' RLS 15410 tag in 12" (dead) Maple | | N8°W 11.09', P.S. 22428 tag in 9" Maple |
| | | | N85°E 2.68' " " " 9" Maple |
| | | | S14°E 13.29' " " " 8" Maple |
| | | | S47°W 30.47' " " " 9" Maple |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | | |
|----|-----------------------------------------------------------------------------------------------------|----|-----------------------------------------|
| G8 | 3/4" pipe at very old fence corner post set P.S. 21559 cap in pipe | G9 | 1" pipe, & P.S. 21559 cap in pipe |
| | N11°W 48.42' RLS 15410 tag in 7" Ironwood in group of four | | Witnesses: |
| | N49°W 28.68' RLS 15410 tag in 12" (dead) Maple | | N8°W 11.09', P.S. 22428 tag in 9" Maple |
| | N45°W 7.9' P.S. 21559 cap in 4" Maple | | N85°E 2.68' " " " 9" Maple |
| | N20°W 25.60' P.S. 21559 cap in 4" shagbark Hickory | | S14°E 13.29' " " " 8" Maple |
| | S80°W 7.4' P.S. 21559 cap in 2" shagbark Hickory | | S47°W 30.47' " " " 9" Maple |
| | corner falls at Westerly edge of open area, second growth to West, is accessible 2 rut road from SE | | |

Signed by *James A. Beck*
 James A. Beck P.S. 21559
 Surveyor's Michigan License No. _____



Date Nov. 6, 2000

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
 REVISED MAY 14, 1979
 REVISED JAN., 1983

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *Norman J. Ossie*
 Date 12-16-00