

FEB 12 2001

2000 PRESQUE ISLE COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Presque Isle Located In: Corner Code #
(County)

1. Public Land Survey T 35 N R 2E H-5
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

PRESQUE ISLE COUNTY
RECORDED
2000 DEC 11 AM 9:52
Janet M. Jamst
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald Bischer, in a field survey on 10/26/00g do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:


	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5								●					
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Aug. 1855 George Cannon set wood post and 2 witnesses
1934+- Marcus Schaaf #3104 Set 1 3/4" pipe in conc built fire line E/W
May 1973 Delmer Porter #15410 found 1 3/4" pipe left 2 witnesses
Nov. 1978 Delmer Porter #15410 found 1 3/4" pipe in conc. replaced with remon mon left 1 new witness + 2 old witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
found Remon mon and 3 old witnesses



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Oct. 26, 2000
Remon Mon

N80° E 49.90' 12" Oak O.W.
N45° W 20.62' 6" Jack Pine O.W.
S80° W 52.75' 24" White Pine O.W.
S24° W 30.10' 14" Norway

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Norman J. Conner*
Date 12-11-00

Signed by Ronald R. Bischer
Surveyor's Michigan License No. 22428

Date 11-7-2000