

2354

PRESQUE ISLE COUNTY RECORDED

2000 PRESQUE ISLE COUNTY, STATE OF MICH., REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

2000 OCT 30 PM 3:28

Janet M. Lamb REGISTER OF DEEDS

For corners in

Table with columns: Presque Isle (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

SURVEY & REMONUMENTATION

FEB 12 2001

SECTION Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Delmer E. Porter, in a field survey on 09/6/00, 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Contains numerical values and two black dots in the grid.

A. Description of original monument and accessories and/or subsequent restoration:

J-9
1" PIPE
52.75' TO E-W FE
82.75' TO N-S FE
N 05° E 55.29' 6" BIRCH
N 60° W 98.92' FE COR
N 80° W 108.56' 9" BIRCH
S 15° W 71.55' 8" BIRCH

J-11
1" PIPE
N 26° E 51.88' 11" POPLAR
N 40° W 79.98' 12" TWIN ELM
N 61° W 58.47' 6" APPLE
NORTH 18.62' FE COR
SOUTH 28.42' FE COR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9
FOUND 1" PIPE
NO WITNESSES REMAINING
LOCATED FROM PREVIOUS SURVEYS



J-11
FOUND 1" PIPE
N 49° W 55.69' 8" POPLAR (BISCHER TAG)
S 43° W 29.95' TWIN ELM 11" (BISCHER TAG)
S 03° W 28.40' FE COR (BISCHER TAG)

Ratified by Peer Group in accordance with P.A. 345

Chairman [Signature]

Date 10/27/00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9
1" PIPE
S 84° W 73.15' 9" MAPLE
N 23° W 69.40' 12" POPLAR
N 19° E 61.10' 4" BALSAM
S 57° E 51.87' 8" BIRCH

J-11
1" PIPE
N 49° W 55.69' 8" POPLAR
S 43° W 29.95' 11" TWIN ELM
S 03° W 28.40' FE COR
N 09° E 29.17' 6" POPLAR

\*WITNESS TAGS & NAILS USED.

Signed by [Signature]
Surveyor's Michigan License No. 15410

Date 10/500