

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
PRESQUE ISLE

(County)

Located In:

Corner Code #

1. Public Land Survey	T 35N R 2E	K 7
	T 35N R 2E	K 8 ✓
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Janet M. Jamb
REGISTER OF DEEDS

SURVEY &
REMONUMENTATION

FEB 12 2001

SECTION
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James A. Beck, in a field survey on Oct 3, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K 7 Nov. 9, 1979 P.A. 74 (Land Corner Recordation)
Certificate by Delmer Porter P.S. 15410
1/2" rod and cap in monument box
N57°W 78.40' 8" Birch
S43°E 48.53' fe. cor.
S56°W 55.30' P. pole

K 8 November 29, 1978 P.A. 74 Certificate by Delmer Porter
1" bar (Delamater 1944)
N49° 59.3 3' Maple
S11°E 113.2' 4" Apple
S67°W 57.09' 12" Apple
S77°W 74.03' 12" Maple
S86°E 33.50' fe. corner

NOTE: Witness card furnished by Porter's Survey includes " FOUND 1" ROD 13°E OF C OF RD 18" DEEP, RAISED WITH 1/2" ROD

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K 7 October 3, 2000 Remonumentation
Found 1/2" iron and mushroomed cap in monument box
Set P.S. 21559 cap
S56°W 55.30' R.L.S. 15410 tag in power pole

K 8 October 3, 2000 Remonumentation
Found 1/2" iron rod, set P.S. 21559 cap on rod
Witnesses found:
S67°W 57.09 12" Multi-stem Apple
S77°W 74.25' 15410 tag in South most stem of 12" Maple

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Norman J. Quine*

Date 12-11-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K 7 October 3, 2000 Remonumentation
1/2" iron and P.S. 21559 cap in monument box
Witnesses:
S56°W 55.30' R.L.S. 15410 tag in power pole
N81°W 90.6' 21559 tag in 8" Birch
N26°W 53.0', near face of road sign post
N28°E 63.10' P.S. 21559 tag in 3" twin Maple
S40°E 47.30' P.S. 21559 tag in new fence corner post

K 8 October 3, 2000 Remonumentation
1/2" iron rod and P.S. 21559 cap
Witnesses:
S67°W 56.83' P.S. 21559 tag in 12" Multi-stem Apple
S77°W 74.25' 15410 tag in South most stem of 12" Maple
N83°W 42.58' P.S. 21559 tag in power pole
N30°E 65.00' P.S. 21559 tag in 4" Cedar in clump
N76°E 28.56' 21559 tag in 5" Maple
N87°E 24.21' 21559 tag in 3" Elm
Corner falls at Ely side of gravel roadway

Signed by James A. Beck P.S. 21559

Surveyor's Michigan License No. _____

Date Nov. 7, 2000

