

649

FEB 12 2001

YEAR 2000 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in PRESQUE ISLE (County)

Located In:

Corner Code -#

1. Public Land Survey	T 35N R 2E	L 5 ✓
	T 35N R 2E	L 7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PRESQUE ISLE COUNTY RECORDED

2000 DEC 11 AM 9:48

James M. Jamb REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, James A. Beck, in a field survey on Oct 9 and Oct 10, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

L 5 October 24, 1974 P.A. 74 (Land Corner Recordation) Certificate by Delmer Porter P.S. 15410  
 fd. 1/2" pipe  
 South 33' fa. cor.  
 N80°W 33.87' 10' Ash  
 N15°E 2.20' 10' Ash clump  
 N85°E 8.06' 10' Twin Maple

L 7 Nov 13, 1979, P.A. 74 (Land Corner Recordation) Certificate by Delmer Porter P.S. 15410  
 1/2" rod in monument box  
 N04°E 41.17' Fence Corner  
 S60°E 82.20' P/Pole  
 N64°E 41.10' Fence Corner  
 N59°E 70.32' Fence Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L 5 October 10, 2000 Remonumentation found 1/2" pipe, set P.S. 21559 cap in pipe  
 Witnesses found:  
 N5°E 2.20' 10' Ash  
 N85°E 8.06' twin 14"-18" Maple

L 7 October 9, 2000 Remonumentation Found 1/2" iron rod in monument box, set cap on rod  
 Witnesses found:  
 S50°E 82.20' old power pole base

Ratified by Peer Group in accordance with P.A. 345

Chairman Norman J. Quinn

Date 12-11-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L 5 October 10, 2000 Remonumentation 1/2" pipe and P.S. 21559 cap  
 Witnesses:  
 N5°E 2.20' P.S. 21559 tag in 10' Ash  
 N85°E 8.06' P.S. 21559 tag in twin 14"-18" Maple  
 N52°W 31.45' P.S. 22435 tag in 16" Maple  
 N16°W 33.70' P.S. 22435 tag in 18" Maple

L 7 October 9, 2000 Remonumentation 1/2" iron rod and P.S. 21559 cap in monument box  
 Witnesses:  
 S50°E 82.20' old power pole base  
 S54°E 81.90' P.S. 21559 tag in new power pole  
 S33°E 83.75' P.S. 21559 tag in 4" Maple  
 S19°E 84.50' P.S. 21559 tag in 5" Maple  
 S1°W 76.65' P.S. 21559 tag in 7" Maple  
 in cluster of four  
 Corner falls in North lane of Blacktop highway

Corner falls at old tree/fence line at N side of lane East and at East side of 2 rut road to North

Signed by James A. Beck P.S. 21559

Date Nov. 7, 2000

Surveyor's Michigan License No. \_\_\_\_\_

