

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
PRESQUE ISLE

(County)

Located In:

Corner Code ≠#

- |                                    |                             |            |
|------------------------------------|-----------------------------|------------|
| 1. Public Land Survey              | T <u>36N</u> R <u>2E</u>    | <u>C-9</u> |
|                                    | T _____ R _____             | _____      |
|                                    | T _____ R _____             | _____      |
|                                    | T _____ R _____             | _____      |
| 2. Property Controlling in Section | S <u>29</u> T _____ R _____ | <u>1</u>   |
|                                    | S _____ T _____ R _____     | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____     | _____      |
|                                    | S _____ T _____ R _____     | _____      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9		•											
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL T. KIISKILA, in a field survey on JANUARY 29, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
C-9 1

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
C-9 1

FOUND AND ACCEPTED A PRESQUE ISLE CO. MON. FOR THE NW COR OF SEC. 29. THIS COR WAS RECORDED PER ACT 74, PA 1970, BY DELMAR PORTER L.S., ON PAGE 342 OF PRESQUE ISLE CO. L.C.R.C. THE MONUMENT IS LOCATED IN THE CENTER OF N-S & E-W TRAIL ROAD INTERSECTION.

ESTABLISHED THE NW COR OF THE NE1/4 OF THE NW1/4 OF SEC. 29 PER STANDARD BLM INSTRUCTIONS.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9  
 FOUND PRESQUE ISLE CO. MON. AT INTER. OF TRAILS ROADS, N-S-E-W.  
 8" ASPEN N44°E 26.92'  
 10" MAPLE S45°E 16.69'  
 12" OAK S05°W 40.70'  
 18" OAK N74°N 27.64'  
 SET CARSONITE POST S45°W 33' +/-

1  
 SET 5/8" x 32" REROD W/CAP.  
 10" W.PINE N12°W 5.23'  
 16" W.PINE N75°E 23.25'  
 7" W.PINE S54°W 36.59'  
 CTR TRAIL ROAD SOUTH 3.5' +/-  
 SET CARSONITE POST NORTH 10' +/-

8 - OLD WIT BY D. PORTER

Signed by Carl T. Kiiskila Date 2-27-97

Surveyor's Michigan License No. 33981