

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
PRESQUE ISLE

(County)	Located In:	Corner Code =#
1. Public Land Survey	T <u>36N</u> R <u>2E</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>29</u> T _____ R _____	<u>5</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, CARL T. KIISKILA, in a field survey on JANUARY 29, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
D-9 5

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
D-9 5

FOUND & ACCEPTED A PRESQUE ISLE CO MON FOR THE NW1/4 COR OF SEC 29. THIS COR WAS RECORDED PER ACT 74, P.A. 1970 BY DELMAR PORTER, L.S. ON PAGE 342 OF PRESQUE ISLE CO. L.C.R.C.'S. THE MON IS LOCATED ON THE E. EDGE OF A TRAIL ROAD NORTH & ON THE N EDGE OF AN E-W TRAIL RD.

ESTABLISHED THE SE CORNER OF THE NE1/4 OF THE NW1/4 OF SEC. 29 PER STANDARD BLM INSTRUCTIONS



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9  
 FOUND PRESQUE ISLE CO MON.  
 114° R.PINE N26°W 43.66'  
 16° W.PINE N68°E 18.52'  
 18° W.PINE S54°E 30.87'  
 112° W.PINE S15°W 39.74'  
 SET CARSONITE POST SOUTH 33' +/-

5  
 SET 3/8" x 32" REROD W/CAP, SET CARSONITE POST 1' +/- NORTH.  
 7° R.PINE S20°W 32.62'  
 5° J.PINE S74°E 51.39'  
 16° DAK N40°E 25.95'  
 10° DAK N26°W 56.18'

\* OLD WIT - PORTER

Signed by Carl T. Kiiskila Date 2-27-97  
 Surveyor's Michigan License No. 33981