

2196

1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION SURVEY & MONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 316 PAGE 279

For corners in Presque Isle (County)

JAN 17 1996

Located In:

Corner Code -#

COMMISSION

- 1. Public Land Survey T 36N R 2E A-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

PRESQUE ISLE COUNTY RECORDED

95 OCT 20 PM 4: 23

Janet M. Lamb REGISTER OF DEEDS Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

I, Norman J. Quaine, in a field survey on March 31, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-1
GLO Notes March 29-30, 1968
Resurvey 1854 Lyle Barden
Hemlock 12" N46° E 13 Abitibi forester
Hemlock 8" S82° E 20 Fd. New Wood Stake
George H. Cannon and brushed line to west

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1
March 31, 1995 Fd. 3" cedar stake broken flush with ground, in line with old brush line to the west.
Presque Isle County Believe to be stake mentioned by
State Remonumentation Abitibi Foresters. Two old stumps,
Norman J. Quaine #33984 a 14" & 16", possibly O.B.T.'s
Porter's survey P.C. Set 1/2" rod & Cap #33984

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1
Left 1/2" Rod & Cap #33984
S29° E 3.98' 6" Cedar
S51° W 34.39' 7" Cedar
N89° W 11.87' 8" birch
N23° W 9.00' 9" Maple

Ratified by Peer Group in accordance with P.A. 345
Chairman [Signature]
Date 9/20/95

*witness tags & nails used.

Signed by Norman J. Quaine Date OCTOBER 19, 1995
Surveyor's Michigan License No. 33984