

2193

SURVEY &

1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

JAN 17 1996 LAND CORNER RECORDATION CERTIFICATE

LIBER 316 PAGE 276

Filing Requirement of Act 74, Mich. P.A. 1970

PRESQUE ISLE COUNTY RECORDED

For corners in Presque Isle (County)

COMMISSION

Located In:

Corner Code =#

95 OCT 20 PH 4: 23

- 1. Public Land Survey T 36N R 2E A-2
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

Janet M. Lamb REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Norman J. Quaine, in a field survey on April 4, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-2
- GLO Notes
- Resurvey 1856
- Hemlock 20" N34 1/2° W 28
- Hemlock 19" S57 1/2° W 19
- George H. Cannon

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-2
- April 4, 1995
- Presque Isle County
- State Remonumentation
- Norman J. Quaine #33984
- Porter's Survey P.C.
- Fd. no evidence of corner's position
- Set 1/2" Rod & Cap #33984
- By single proportion

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-2
- Left 1/2" Rod & Cap #33984
- N23°W 46.44' 9" N. Pine
- N64°W 47.64' 9" N. Pine
- S05°E 46.86' 8" Aspen
- N53°E 46.69' 8" Aspen

Ratified by Peer Group in accordance with P.A. 345 Chairman [Signature] Date 9/20/95

* Witness tags & nails used.

Signed by Norman J. Quaine Date OCTOBER 19, 1995 Surveyor's Michigan License No. 33984