

2192 -- SURVEY & MONUMENTATION
 1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

JAN 17 1996 LAND CORNER RECORDATION CERTIFICATE

LIBER 316 PAGE 275

For corners in COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

PRESQUE ISLE COUNTY
 RECORDED

95 OCT 20 PM 4: 23

Janet M. Lamb
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Presque Isle (County)	Located In:	Corner Code #/
1. Public Land Survey	T 36N R 2E	A-3
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman J. Quaine in a field survey on March 31, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3		
GLO Notes	11-6-78	Fd 2 1/2" Pipe
Resurvey 1856	Presque Isle County	Replaced w/conc mon/brass cap
Sp. Pine 13" S73°W 14½	Local Remonumentation	N65°E 43.01' 5" Oak
Sp. Pine 8" N55°W 48	LCRC Page 340	N48°W 45.39' 6" N. Pine
George H. Cannon	Delmer E. Porter	S66°W 52.78' 7" J. Pine
	#15410	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3	
March 31, 1995	Fd. Conc Mon/brass cap
Presque Isle County	N46°W 45.62' 9" N. Pine
State Remonumentation	N74°E 42.91' 6" Oak
Norman J. Quaine	S68°W 42.89' 10" J. Pine
#33984	
Porter's Survey P.C.	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3
 Left Conc Mon/Brass Cap
 N46°W 45.62' 9" N. Pine
 N74°E 42.91' 6" Oak
 S68°W 42.89' 10" J. Pine
 S70°E 44.79' 6" J. Pine

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *Delmer E. Porter*
 Date 9/20/95

*Witness tags & nails used.

Signed by Norman J. Quaine Date OCTOBER 19, 1995
 Surveyor's Michigan License No. 33984