

2197

SURVEY &

1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

JAN 17 1996 LAND CORNER RECORDATION CERTIFICATE

LIBER 316 PAGE 280

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Presque Isle (County)

COMMISSION

Located In: Corner Code #:

- 1. Public Land Survey T 36N R 2E A-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

PRESQUE ISLE COUNTY REGISTERED

95 OCT 20 PM 4:26

Janet M. Sams REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Norman J. Quaine, in a field survey on March 31, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-5 GLO Notes Resurvey 1856 Sp. Pine 8" N25°W 59 Sp. Pine 8" S60°W 46 George H. Cannon 11-6-78 Presque Isle County Local Remonumentation LCRC Page 340 Delmer E. Porter #15410 Fd. 2" Pipe Replaced w/conc mon/brass cap N62°W 54.45' 8" N. Pine S73°W 45.20' 5" N. Pine S34° E 37.82' P. Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5 March 31, 1995 Presque Isle County State remonumentation Norman J. Quaine #33984 Porter's Survey P.C. Fd. conc Mon/Brass Cap S72°W 45.02' 9" N. Pine N60°W 54.53' 12" N. Pine S33°E 37.85' P. Pole

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 Left conc Mon/Brass Cap S72°W 45.02' 9" N. Pine N60°W 54.53' 12" N. Pine N52°E 59.69' 12" W. Pine S33° E 37.85' P. Pole

Ratified by Peer Group in accordance with P.A. 345

Chairman Delmer E. Porter

Date 9/20/95

\*Witness tags & nails used.

Signed by Norman J. Quaine Surveyor's Michigan License No. 33984

Date OCTOBER 19, 1995