

State of Michigan Remonumentation Program  
For Presque Isle County

PRESQUE ISLE COUNTY  
RECORDED

LAND CORNER RECORDATION CERTIFICATE 94 SEP -6 AM 10:10  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle Located In: Corner Code #  
(County)

1. Public Land Survey T 36N R 2E A-7  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Jane M. Samba*  
REGISTER OF DEEDS

LIBER 311 PAGE 117

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman J. Quaine in a field survey on April 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7 Y. Pine 16" N71½°W 3.00 Lks.  
GLO Notes Y. Pine 16" S14 3/4°W 79½ Lks.  
Resurvey 1856 Y. Pine 16" N87°45'W 12.81 Lks.  
11-6-78 Fd. 1" Pipe  
Presque Isle County Reset position with 4" concrete  
Local Remonumentation Monument with brass cap lettered  
Project "Presque Isle County Remonumentation"  
L.C.R.C. Pg. 341 N72°E 59.74' 6" Jack Pine  
Delmer E. Porter N33°W 48.09' 8" Jack Pine  
LLS#15410 N69°W 47.46' 6" Jack Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7  
4-7-94 Found 1/2" Rod in Mon. Box  
P. I. County N38°W 65.68' 9" Jack Pine  
St. Remon. N51°E 77.92' 9" Jack Pine  
Norman J. Quaine Put cap #15410 on 1/2" Rod  
#33984, Porter's  
Survey, P.C.

"A" continued:

5-28-87 Found evidence by a Doyle  
L.C.R.C. Cheboygan Survey from 1952, that the  
County corner located 11-6-78 was  
Delmer E. Porter 33' North of the true corn-  
LLS#15410 position. Moved Conc. Mon.  
w/brass cap to true position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 N50°E 78.00' 6" Jack Pine  
1/2" Rod & Cap #15410 in Mon. Box N17°W 76.94' 8" Jack Pine  
N38°W 65.68' 9" Jack Pine N25°W 70.00' 12" Jack Pine  
N51°E 77.92' 9" Jack Pine N37°W 65.21' 6" Jack Pine  
S34°W 103.31' 12" Aspen  
S30°E 96.08' 9" Jack Pine

Ratified by Peer Group  
in accordance with P.A. 345  
Chairman *Delmer E. Porter*  
Date July 27, 1994

Signed by Norman J. Quaine Date Aug 17, 1994  
Surveyor's Michigan License No. 33984