

State of Michigan Remonumentation Program  
For Presque Isle County

PRESQUE ISLE COUNTY  
RECORDED

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

94 SEP -6 AM 10:10

For corners in

Presque Isle  
(County)

Located In:

Corner Code #

*Jane M. Lamb*  
REGISTER OF DEEDS

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>36N</u> R <u>2E</u> | <u>A-8</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

LIBER **311** PAGE **118**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman J. Quaine in a field survey on April 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-8  
GLO Notes Aspen 12" N40°W 28 Lks.  
Resurvey 1856 W. Pine S52°W 5 Lks.  
May 28, 1987 Found 2" Pipe and old  
L.C.R.C. 4"X4" Stake  
Cheboygan County N01°W 29.32' 8" Maple  
M-8 T36N, R1E N74°E 35.65' Power Pole  
Delmer E. Porter S15°E 27.45' 5" Balsam  
LLS#15410 S65°W 15.05' 3" Balsam

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8  
4-7-94 Found 2" Pipe  
Presque Isle County N73°E 35.55' P. Pole  
State Remonumentation S12°E 27.40' 9" Balsam  
Norman J. Quaine N03°W 29.35' 11" Maple  
#33984, Porter's  
Survey P.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8  
2" Pipe  
N73°E 35.55' P. Pole  
S12°E 27.40' 9" Balsam  
N03°W 29.35' 11" Maple  
S49°W 8.14' 3" Balsam

Ratified by Peer Group  
in accordance with P.A. 345  
Chairman *Delmer E. Porter*  
Date July 27, 1994

Signed by *Norman J. Quaine* Date Aug. 17, 1994  
Surveyor's Michigan License No. 33984