

State of Michigan Remonumentation Program
For Presque Isle County

PRESQUE ISLE COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 SEP -6 AM 10:10

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>36N</u> R <u>2E</u>	<u>B-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Janet M. Lamb
REGISTER OF DEEDS

LIBER **311** PAGE **119**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ SECTION _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman J. Quaine in a field survey on May 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-7
GLO Notes Y. Pine 14" S29° W 20 Lks.
Resurvey 1856 Y. Pine 14" N63° W 23 Lks.
Local Presque Isle Replaced 2" Pipe
Co. Remonumentation Conc. Mon. & Brass Cap
Project 11/6/78 N07° W 48.37' 4" J. Pine
S46° W 24.99' 7" J. Pine
S43° E 19.63' 8" J. Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7
5-18-94 Fd. Conc. Mon. & P.I. Co.
Presque Isle County Remon. Brass Cap
State Remonumentation S48° E 19.59' 7" Jack Pine
Norman J. Quaine N05° W 48.12' 6" Jack Pine
#33984, Porter's S67° W 107.68' 10" Jack Pine
Survey, P.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7
Conc. Mon. & P.I. Co.
Remon. Brass Cap
S48° E 19.59' 7" Jack Pine
N05° W 48.12' 6" Jack Pine
N67° W 107.68' 10" Jack Pine
S56° W 19.58' 5" Jack Pine

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmer E. Porter*
Date July 27, 1994

Signed by *Norman J. Quaine* Date Aug 17, 1994

Surveyor's Michigan License No. 33984