

**SURVEY &
DOCUMENTATION**

1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION
JAN 17 1995

PRESQUE ISLE COUNTY
RECORDED

95 OCT 20 PH 4: 26

**LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>36N</u> R <u>2E</u>	<u>C-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Jane M. Lamb
REGISTER OF DEEDS

LIBER **316** PAGE **285**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman J. Quaine, in a field survey on April 4, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1
GLO Notes
Resurvey 1856
Cedar 13" N52½° E 32
Cedar 16" N70° W 19
George H. Cannon

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1
April 4, 1995 Fd. no evidence to corner's position
Presque Isle County Set 1/2" Rod & Cap #33984
State Remonumentation By single proportion
Norman J. Quaine #33984
Porter's Survey P.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1
Left 1/2" Rod & Cap #33984
S62° E 5.07' 4" Aspen
S88° W 8.34' 3" Aspen
N27° W 44.82' 5" Aspen
N21° E 53.48' 6" Cedar

Ratified by Peer Group
in accordance with P.A. 345
Chairman *[Signature]*
Date 9/20/95

*Witness tags & nails used.

Signed by *Norman J. Quaine* Date OCTOBER 19, 1995
Surveyor's Michigan License No. 33984