

SURVEY &

MONUMENTATION

1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION PRESQUE ISLE COUNTY
RECORDED
JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

95 OCT 20 PM 4:26

For corners in

Janet M. Leimb
REGISTER OF DEEDS

Presque Isle (County)	Located In:	Corner Code #
1. Public Land Survey	T 36N R 2E	C-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 316 PAGE 286

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman J. Quaine in a field survey on May 8, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-2
GLO Notes
Resurvey 1856
Beech 16" S60½°W 35
Beech 16" S65°E 40½
George H. Cannon

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-2
May 8, 1995 Fd. no evidence of corner's position
Presque Isle County Set 1/2" Rod & Cap #33984
State Remonumentation By Single Proportion
Norman J. quaine #33984
Porter's Survey P.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2
Left 1/2" Rod & Cap #33984
S89°E 15.47' 6" Maple
N34°W 14.69' 8" Twin Maple
S13°W 43.36' 6" Maple
S88°W 45.25' 9" Maple

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Belmont Porter*
Date 9/20/95

*Witness tags & nails used.

Signed by Norman J. Quaine
Surveyor's Michigan License No. 33984

Date: OCTOBER 19, 1995