

0004 SURVEY & MONUMENTATION
 1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE

LIBER 316 PAGE 287

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Presque Isle
 (County)

Located In:

Corner Code -#

- | | | | | | |
|------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey | T | 36N | R | 2E | C-4 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

PRESQUE ISLE COUNTY
 RECORDED

95 OCT 20 PM 4:27

Janet M. Lamb
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman J. Quaine in a field survey on April 12, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-4		
GLO Notes	11-6-78	Fd. 1 3/4" Pipe in sand trail
Resurvey 1856	Presque Isle County	Replaced w/conc mon/brass cap
Beech 10" N25° E 43	Local Remonumentation	N82° E 37.21' 9" N. Pine
Hemlock 22" N57 1/2° W 41	LCRC Page 342	S36° E 27.14' 10" W. Pine
George H. Cannon	Delmer E. Porter	S35° W 56.35' 5" N. Pine
	#15410	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4	
April 12, 1995	Fd. conc mon/brass cap
Presque Isle County	in C/L of N-S fire lane
State Remonumentation	N85° E 37.33' 13" N. Pine
Norman J. Quaine #33984	S33° E 27.16' 15" W. Pine
Porter's Survey P.C.	S37° W 56.40' 6" N. Pine

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4
 Left Conc Mon/Brass Cap
 N85° E 37.33' 13" N. Pine
 S33° E 27.16' 15" W. Pine
 S37° W 56.40' 6" N. Pine
 N56° E 38.27' 13" Ash

Ratified by Peer Group
 in accordance with P.A. 345

Chairman *Delmer E. Porter*

Date 9/20/95

*Witness tags & nails used.

Signed by Norman J. Quaine
 Surveyor's Michigan License No. 33984

Date OCTOBER 19, 1995