

**SURVEY &
MONUMENTATION**

2205

1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION
JAN 17 1996

**LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

PRESQUE ISLE COUNTY
RECORDED

95 OCT 20 PM 4: 27

Janet M. Lamb
REGISTER OF DEEDS

LIBER **316** PAGE **288**

Register of Deeds Stamp & File Number

For corners in

| | | |
|---------------------------------------|-------------------|----------------|
| <u>Presque Isle</u> (County) | Located In: | Corner Code -# |
| 1. Public Land Survey | T <u>36NR2E</u> | <u>C-5</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Norman J. Quaine in a field survey on April 5, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|------------------------|-----------------------|-------------------------------|
| C-5 | | |
| GLO Notes | 11-6-78 | Fd 3" Pipe at inter. of |
| Resurvey 1856 | Presque Isle County | Two fire lanes (N-S-E-W) |
| Black Oak 9" S81°W 16 | Local Remonumentation | Replaced w/conc mon/brass cap |
| W. Pine 18" N71½°E 139 | LCRC Page 342 | N51°E 21.68' 8" N. Pine |
| George H. Cannon | Delmer E. Porter | S41°E 31.50' 5" Oak |
| | #15410 | S25°W 38.97' 7" Oak |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

| | |
|-------------------------|--------------------------------------|
| C-5 | |
| April 5, 1995 | Fd. Conc mon/brass cap |
| Presque Isle County | at C/L of fire lane inter. (N-S-E-W) |
| State Remonumentation | S39°E 31.54' 9" Oak |
| Norman J. Quaine #33984 | N54°E 21.78' 14" N. Pine |
| Porter's Survey P.C. | S26°W 38.97' 10" Oak |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5
Left conc Mon/Brass Cap
S39°E 31.54' 9" Oak
N54°E 21.78' 14" N. Pine
S26°W 38.97' 10" Oak
N58°W 26.67' 16" Oak

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmer E. Porter*
Date 9/20/95

*Witness tags & nails used.

Signed by Norman J. Quaine Date October 19, 1995
Surveyor's Michigan License No. 33984