

2206

SURVEY & DOCUMENTATION

1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION
JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 316 PAGE 289

For corners in

Presque Isle (County)	Located In:	Corner Code #/
1. Public Land Survey	T 36N R 2E	C-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

PRESQUE ISLE COUNTY
RECORDS

95 OCT 20 PM 4: 27

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18	●	17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman J. Quaine, in a field survey on April 5, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-6		
GLO Notes	11-6-78	Fd 2" Pipe at inter. of
Resurvey 1856	Presque Isle County	two fire lanes (N-S-E-W)
Y. Pine 13" N26°41'E 487½	Local Remonumentation	Replaced w/conc mon/brass cap
Y. Pine 12" S21°10'W 384	LCRC Page 342	N38°E 23.46' 8" N. Pine
George H. Cannon	Delmer E. Porter	N53°W 13.81' 8" N. Pine
	#15410	S25°W 17.93' 5" J. Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6		
April 5, 1995	Fd. Conc Mon/Brass Cap	
Presque Isle County	at C/L of fire lanes (N-S-E-W)	
State Remonumentation	N37°E 23.45' 17" N. Pine	
Norman J. Quaine #33984	N52°W 13.87' 16" N. Pine	
Porter's Survey P.C.	S29°W 18.03' 9" J. Pine	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6
Left conc Mon/Brass Cap
N37°E 23.45' 17" N. Pine
N52°W 13.87' 16" N. Pine
S29°W 18.03' 9" J. Pine
S77°W 35.15' 8" N. Pine

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmer E. Porter*
Date 9/20/95

*Witness tags & nails used.

Signed by Norman J. Quaine
Surveyor's Michigan License No. 33984

Date OCTOBER 19, 1995