

State of Michigan Remonumentation Program  
For Presque Isle County

PRESQUE ISLE COUNTY  
RECORDED

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

94 SEP -6 AM 10:10

For corners in  
Presque Isle  
(County)

Located In: Corner Code #

*Jane M. Lamb*  
REGISTER OF DEEDS

- 1. Public Land Survey T 36N R 2E C-8  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

LIBER 311 PAGE 121

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman J. Quaine in a field survey on April 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-8  
GLO Notes W. Pine 22" N64°W 27 Lks.  
Resurvey 1856 Y. Pine 18" S51°E 86 Lks.  
2-25-94 Found no evidence indicating  
L.C.R.C. Presque Isle corner's position  
County Set 1/2" Rod & Cap #15410  
Norman J. Quaine By single proportion  
#33984, Porter's N13°E 79.84' 18" White Pine S13°E 31.74' 12" Nor. Pine  
Survey, P.C. S41°E 31.06' 12" Norway Pine S40°W 77.46' 10" Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8  
4-7-94 Found 1/2" Rod & Cap #15410  
Presque Isle County N13°E 79.84' 18" White Pine  
State Remonumentation S41°E 31.06' 12" Norway Pine  
Norman J. Quaine S13°E 31.74' 12" Norway Pine  
S40°W 77.46' 10" Oak

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8  
1/2" Rod & Cap #15410  
N13°E 79.84' 18" White Pine  
S41°E 31.06' 12" Norway Pine  
S13°E 31.74' 12" Norway Pine  
S40°W 77.46' 10" Oak

Ratified by Peer Group  
in accordance with P.A. 345  
Chairman *Robert E. Porter*  
Date July 27, 1994

Signed by *Norman J. Quaine*  
Surveyor's Michigan License No. 33984

Date Aug 17, 1994