

State of Michigan Remonumentation Program
For Presque Isle County

PRESQUE ISLE COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE 94 SEP -6 AM 10:10
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle Located In: Corner Code #
(County)

1. Public Land Survey T 36N R 2E C-9
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Janet M. Lamb
REGISTER OF DEEDS

LIBER 311 PAGE 122

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat SECTION
5. Private Claims _____

I, Norman J. Quaine in a field survey on April 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-9
GLO Notes Y. Pine 14" S60°W 6 Lks.
Resurvey 1856 Y. Pine 12" N35°E 96 Lks.
11-6-78 Found "T" Iron at the
Presque Isle County Inter. of Two Sands trails.
Local Remonumentation Assumed to be Delameter-Muschell Cor.
L.C.R.C. #342 Reset with concrete monument N18°W 51.97' 7" Maple-clump
Delmer E. Porter and brass cap lettered S55°W 30.83' 7" W. Pine
LLS#15410 "P.I. Co. Remon." S48°E 16.48' 7" Maple-clump

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9
4-7-94 Found conc. Mon. & P.I. Co.
Presque Isle County Remon. Brass Cap
State Remonumentation S49°E 16.73' 10" Maple
Norman J. Quaine N18°W 51.79' 9" Maple in poor condition
#33984, Porter's
Survey P.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9
Conc. Mon. & P. I. Co.
Remon. Brass Cap
N41°E 27.13' 7" Aspen
S49°E 16.73' 10" Maple
S73°W 60.55' 5" White Pine
N74°W 27.88' 16" Oak

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmer E. Porter*
Date July 27, 1994

Signed by *Norman J. Quaine* Date Aug 17, 1994
Surveyor's Michigan License No. 33984