

State of Michigan Remonumentation Program  
For Presque Isle County

PRESQUE ISLE COUNTY  
RECORDED

LAND CORNER RECORDATION CERTIFICATE 94 SEP -6 AM 10:10  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>36N</u> R <u>2E</u>	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	<u>JAN 22 2001</u>

*Janet M. Lamb*  
REGISTER OF DEEDS  
Sep #1  
LIBER 311 PAGE 123  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

SECTION

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Norman J. Quaine in a field survey on April 7, 1994, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-10			
GLO Notes	Cedar 12" N60°W 17 Lks.	Jan 4, 1988	Fd. 1" Pipe in place
Resurvey 1856	W. Birch 9" East 25 Lks.	L.C.R.C.	Witnessed by Del Porter
1968	1/2" Rod by Post	Carl Johnson	LS
Porter's Survey	S80°W 10.32' 7" Balsam	LS#30083	Set DNR Mon. & Cedar
Corner Records	N85°E 8.70' 4" Spruce		Post
	N40°W 18.64' 8" Spruce		7" Cedar S30°W 15.3'
	Not Recorded		3" Cedar S59°E 19.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10	
4-7-94	FD. 1" Pipe with D.N.R.
Presque Isle County	metal disk & squared cedar post
State Remonumentation	S26°W 15.85' 7" Cedar
Norman J. Quaine	N88°W 10.11' 7" Dead Balsam
#33984, Porter's Survey, P.C.	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10  
1" Pipe with D.N.R.  
metal disk by squared cedar post  
S26°W 15.85' 7" Cedar  
N51°W 23.96' 3" Aspen  
N01°W 32.02' 4" Aspen  
S73°E 18.33' 7" Spruce

Ratified by Peer Group  
in accordance with P.A. 345  
Chairman *Del Porter*  
Date July 27, 1994

Signed by Norman J. Quaine Date Aug 17, 1994  
Surveyor's Michigan License No. 33984