

State of Michigan Remonumentation Project 1994  
Presque Isle County, Michigan

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

PRESQUE ISLE COUNTY  
RECORDED

94 SEP -6 AM 10:10

For corners in

Presque Isle Located In: Corner Code #  
(County)

1. Public Land Survey T 36N R 2E C-10  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Reg. #2*

*Janet M. Lamb*  
REGISTER OF DEEDS

LIBER **311** PAGE **115**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Norman J. Quaine in a field survey on April 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
C-10

GLO Notes	Cedar 12" N60°W 17 Lks.	Jan. 4, 1988 L.C.R.C. by Carl Johnson LS#30083
Resurvey 1856	W. Birch 9" East 25 Lks.	Found 1" Pipe in place by Delmer Porter LS
1968 Porter's Survey Records		Set DNR Mon. & Cedar Post
1/2" Rod by Post		7" Cedar S30°W 15.3'
S80°W 10.32' 7" Balsam		3" Cedar S59°E 19.3'
N85°E 8.70' 4" Spruce		
N40°W 18.64' 8" Spruce		
Not Recorded		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10  
4-7-94  
Found 1" Pipe with DNR Metal Disk & Squared Cedar Post  
Found S26°W 15.85' 7" Cedar (Johnson)  
Found N88°W 10.11' 7" Dead Balsam (Porter)

Confusion as to if corner & corner position were in the same location. On Aug. 16, 1994, the North 1/2 of the West line of Section 29 was re-run using the Plat of Sherwood Forest as a bearing base. The corner position appears to coincide with existing plat monumentation as it exists on the ground, in the field.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10  
1" Pipe with DNR Disk  
S26°W 15.85' 7" Cedar  
N51°W 23.96' 3" Aspen  
N01°W 32.02' 4" Aspen  
S73°E 18.33' 7" Spruce



Ratified by Peer Group  
in accordance with P.A. 345  
Chairman Delmer E. Porter  
Date August 29, 1994

Signed by Norman J. Quaine  
Surveyor's Michigan License No. 33984

Date August 29, 1994