

State of Michigan Remonumentation Program
For Presque Isle County

PRESQUE ISLE COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 SEP -6 AM 10:10

For corners in

Jane M. Lamb
REGISTER OF DEEDS

Presque Isle (County)	Located In:	Corner Code #
1. Public Land Survey	T 36N R 2E	C-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 311 PAGE 124

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman J. Quaine in a field survey on April 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-11
GLO Notes Ironwood 12" N57° W 44 Lks.
Resurvey 1856 Aspen 13" N39° E 18 Lks.
January 1947 1 1/4" Pipe
Records from Doyle N10° E 39.8' SE cor. cottage
Engineering N02° E 49.94' SW Cor. cottage
Porter Survey Records S88° W 63.87' NE Cor. of cottage
S20° W 39.4' 10" Maple
(Note): Records indicate cor. was found w/conc. slab in 1959 -slab can be lifted.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11
4-7-94 Fd. 1/2" Rod & Cap "A" Continued:
P. I. County (Delameter-Muschell) 1-25-72 1 1/2" Pipe
State Remon. N52° E 36.48' L.C.R.C. Cabin due W. 63.87'
Norman J. Quaine Abandoned P. Pole No signature 10" Maple S20° W 39.41'
#33984, Porter's S78° E 45.60' P. Pole
Survey, P.C. S15° W 45.60' 19" Aspen Sept. 18, 1991 Fd. 1/2" Rod & Cap w/
S14° W 39.43' 14" Aspen L.C.R.C. Pg.839 (Delameter-Muschell)
James H.Granger Cabin due West 63.87'
LS#16041 10" Maple S20° W 39.41'
(Note: Did not address witnesses)
20" Poplar S38° W 39.42'
20" Poplar S13° W 45.57'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 Power Pole S80° E 45.52'
1/2" Rod & Cap (Delameter-Muschell) Abandoned Power Pole
N52° E 36.48' Abandoned P. Pole N50° E 36.39'
S78° E 45.60' P. Pole
S15° W 45.60' 19" Aspen
S14° W 39.43' 14" Aspen

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delameter-Muschell*
Date July 27, 1994

Signed by *Norman J. Quaine*
Surveyor's Michigan License No. 33984

Date Aug 17, 1994