

State of Michigan Remonumentation Program
For Presque Isle County

PRESQUE ISLE COUNTY
RECORDED

**SURVEY &
REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 SEP -6 AM 10: 11

For corners in

Jane M. Lamb
REGISTER OF DEEDS

LIBER 311 PAGE 126

Register of Deeds Stamp & File Number

Presque Isle (County) Located In: Corner Code #

1. Public Land Survey **COMMISSION** T 36N R 2E D-9
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9		●											
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman J. Quaine in a field survey on April 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
D-9
GLO Notes Y. Pine 14" N66°E 27 Lks.
Resurvey 1856 Y. Pine 15" S76°W 71 Lks.
11-6-78 Found 3/4" Pipe at
Presque Isle County Intersection of Two Sand Trails
Local Remonumentation No Witnesses
Project Reset Conc. Monument
L.C.R.C. Pg. 343 with brass cap lettered "Presque S14°W 40.10' 6" W. Pine
Delmer E. Porter Isle County Remonumentation" S57°E 30.93' 5" W. Pine
LLS#15410 N30°W 43.80' 8" N. Pine
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-9
4-7-94 Fd. Conc. Mon. & P. I. Co.
Presque Isle County Remon. Brass Cap
State Remonumentation N30°W 43.70' Norway Pine
Norman J. Quaine S16°W 39.83' 12" White Pine
#33984, Porter's S51°E 30.88' 9" White Pine
Survey, P.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9
Conc. Mon. & P. I. Co.
Remon. Brass Cap
N30°W 43.70' 14" Norway Pine
N65°E 18.57' 5" White Pine
S16°W 39.83' 12" White Pine
S51°E 30.88' 9" White Pine

Ratified by Peer Group
in accordance with R.A. 345
Chairman *Delmer E. Porter*
Date July 27, 1994

Signed by Norman J. Quaine
Surveyor's Michigan License No. 33984

Date Aug 17, 1994