

**SURVEY & DOCUMENTATION**  
**1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION**

**JAN 17 1996**

**LAND CORNER RECORDATION CERTIFICATE**  
**COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

PRESQUE ISLE COUNTY  
RECORDED

95 OCT 20 PH 4: 28

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>36</u> N R <u>2</u> E	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Janet M. Slamb*  
REGISTER OF DEEDS

LIBER **316** PAGE **291**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Norman J. Quaine in a field survey on April 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-1  
 GLO Notes  
 Resurvey 1856  
 W. Pine 9" N65°E 10  
 Aspen 10" N58°W 27  
 George H. Cannon

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1  
 April 5, 1995  
 Presque Isle County  
 State Remonumentation  
 Norman J. Quaine #33984  
 Porter's Survey P.C.

Fd. no evidence of corner's position  
 Set 1/2" Rod & Cap #33984  
 By single proportion

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1  
 Left 1/2" Rod & Cap #33984  
 S58°W 13.77' 4" Aspen  
 N23°E 5.25' 3" Aspen  
 S78°E 9.28' 4" Aspen  
 S10°E 15.68' 4" Aspen

Ratified by Peer Group  
 in accordance with P.A. 345  
 Chairman *Delmar S. Slaton*  
 Date 9/20/95

\*Witness tags & nails used.

Signed by Norman J. Quaine  
 Surveyor's Michigan License No. 33984

Date OCTOBER 19, 1995