

State of Michigan Remonumentation Program
For Presque Isle County

PRESQUE ISLE COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 SEP -6 AM 10:11

SURVEY &
REMONUMENTATION

For corners in

Presque Isle
(County)

Located In:

Corner Code #

APR 25 1995

COMMISSION

- | | | | | | |
|---------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>36N</u> | R | <u>2E</u> | <u>E-9</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling
in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Janet M. Lamb
REGISTER OF DEEDS

LIBER **311** PAGE **129**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman J. Quaine in a field survey on March 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-9
GLO Notes Cedar 8" N15°E 22 Lks.
Resurvey 1856 Cedar 8" S15°W 6 Lks.

Date Unknown 2" Pipe
Information provided N45°E 48.00' DNR Post
by R.S. Scott and S30°E 36.10' 12" White Pine
Associates, Alpena, MI. N70°W 36.62' 6" White Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9
3-7-94 Fd. Conc. Mon. & P.I. Co.
Presque Isle Co. Remon. Brass Cap
State Remon. N51°E 48.00' DNR Red Top Post
Norman J. Quaine N39°W 36.92' 8" White Pine
#33984, Porter's S26°E 36.10' 12" White Pine
Survey P.C.

"A" Continued:

11-6-78

P. I. County

Local Remon.

Project

L.C.R.C. Pg. 352 N51°E 48.00' DNR Post

2" Pipe lost - Set 4" conc.
Mon. and brass cap lettered
"P. I. Co. Remonumentation"

from available witnesses

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9
Conc. Mon. & P. I. Co.
Remon. Brass Cap
N39°W 36.92' 8" White Pine
N13°W 30.90' 9" Cedar
S29°E 36.53' 12" White Pine
S51°W 30.54' 7" Maple

Delmer E. Porter LLS#15410

Note: L.C.R.C., Part "A" Shows
S30°E 38.00' 12" W. Pine
Records in Porter's Survey
office indicate the correct
witness should be
S30°E 36.10' 12" White Pine

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Delmer E. Porter*

Date July 27, 1994

Signed by *Norman J. Quaine* Date Aug 17, 1994

Surveyor's Michigan License No. 33984