

State of Michigan Remonumentation Program
For Presque Isle County

PRESQUE ISLE COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 SEP -6 AM 10:11

For corners in **SURVEY & REMONUMENTATION**
Presque Isle County
(County)

Located In: Corner Code #

Jane M. Lamb
REGISTER OF DEEDS

LIBER 311 PAGE 130

1. Public Land Survey **APR 25 1995**
COMMISSION
T 36N R 2E E-10
T R
T R
T R
2. Property Controlling in Section S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, Norman J. Quaine in a field survey on March 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-10
GLO Notes W. Pine 22" N42°W 87 Lks.
Resurvey 1856 Sp. Pine 12" S20°E 52 Lks.
Date Unknown 3/4" Pipe
Miscellaneous Records No Witnesses 10-17-75 3/4" Pipe
Found by Porter's L.C.R.C. N50°W 11.72' 10"Oak
Survey. Indicate 3/4" Pipe Delmer E. Porter N73°E 30.12' 18"Nor
set by Edward LaCross (Surveyor) LS#15410 S75°E 78.24' 12"Nor
Possibly 1960's

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10
3-7-94 Fd. remains of conc. Mon. 11-6-78 Fd. 3/4" Pipe -
P. I. County 1' Below surface P.I. County replaced w/4" Conc.
State Remon. N77°E 30.12' 19" Norway Pine Local Remon. mon. w/brass cap
Norman J. Quaine S75°E 78.24' 13" Norway Pine L.C.R.C. Pg352 lettered "P.I. CO.
#33984, Porter's N50°W 11.72' 10" oak Delmer E. Porter Remonumentation"
Survey, P.C. Set 1/2" Rod & Cap #15410 LS#15410 N50°W 11.72' 10"Oak
by using witnesses N73°E 30.12' 18"
Replaced two witnesses due N. Pine
to graders hitting them S75°E 78.24' 12"
N. Pine

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10
1/2" Rod & Cap #15410
N77°E 30.12' 19" Norway Pine
S46°E 31.59' 7" Norway Pine
N21°W 37.04' 8" Jack Pine
N86°W 26.20' 7" Jack Pine

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmer E. Porter*
Date July 27, 1994

Signed by *Norman J. Quaine*
Surveyor's Michigan License No. 33984

Date Aug. 17, 1994