

State of Michigan Remonumentation Program
For Presque Isle County

PRESQUE ISLE COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 SEP -6 AM 10:11

For corners in SURVEY &

REMONUMENTATION Located In: _____
(County)

Corner Code #

Janet M. Lamb
REGISTER OF DEEDS

LIBER 311 PAGE 131

Register of Deeds Stamp & File Number

1. Public Land Survey APR 25 1995 T 36N R 2E E-11
T _____ R _____
COMMISSION T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman J. Quaine in a field survey on March 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-11
GLO Notes Y. Pine 16" S75°W 54 Lks.
Resurvey 1856 Y. Pine 14" N52°E 274 Lks.
January 1947 2" Pipe
Doyle Engineering N12°W 51.6' 6" Maple
Records from N22°E 34.38' 10" Oak (Gone 10/24/59)
Misc. files S35°W 67.75' 10" N. Pine
Porter's Survey, P.C.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11
3-7-94 Fd. Conc. Mon. & P.I.Co..
P. I. County Remon. Brass Cap
State Remon. S43°W 69.63' 10" N.Pine
Norman J. Quaine S34°E 68.08' 16" N.Pine
#33984, Porter's N32°E 69.46' 15" Tw.Oak
Survey, P.C.

"A" Continued:

April 25, 1968 Found 2" Pipe, 3' Deep
Survey by Porter's *Raised with 1" Pipe
Survey. Not recorded S45°E 68.10' 16" R. Pine
until 10-17-75 S30°W 69.43' 8" Pine
L.C.R.C. N70°W 81.00' 16" Oak

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Delmer E. Porter LS#15410

E-11	11-6-78	Fd. 1/2" Rod in 3/4" Pipe
Conc. Mon. & P. I. Co.	P. I. County	in 2" Pipe & Two Pine Wit.
Remon. Brass Cap	Local Remon.	Reset position w/4" Conc.
S43°W 69.63' 10" N.Pine	Project	Mon. w.brass cap lettered
S34°E 68.08' 16" N.Pine	L.C.R.C. Pg345	"P.I. County Remon."
N32°E 69.46' 15" Tw. Oak	Delmer E. Porter	N30°E 69.38' 16" Twin Oak
N46°W 54.65' 9" Aspen	LS#15410	S35°E 68.00' 16" N. Pine
		S43°W 69.65' 8" N. Pine

Signed by Norman J. Quaine Date Aug 17, 1994
Surveyor's Michigan License No. 33984

Notified by Peer Group
in accordance with P.A. 345
Chairman Delmer E. Porter

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
Date July 27, 1994
2390