

State of Michigan Remonumentation Program
For Presque Isle County

PRESQUE ISLE COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SEP - 6 AM 10:11

For corners in
**SURVEY &
REMONUMENTATION**
Presque Isle
(County)

Located In: Corner Code #

Janet M. Lamb
REGISTER OF DEEDS

APR 25 1995

- | | | | | | |
|---------------------------------------|---|-----|---|----|------|
| 1. Public Land Survey | T | 36N | R | 2E | E-12 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

LIBER 311 PAGE 132

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman J. Quaine a field survey on April 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | | | |
|-----------------|----------------------------|--------------------|--------------------|
| E-12 | | | |
| GLO Notes | Cedar 14" N59°E 29 Lks. | Oct. 7, 1977 | Recorded Surveys |
| Resurvey 1856 | Cedar 12" S68°W 28 Lks. | Surveys Recorded | show cor. position |
| January 1947 | Concrete Monument | Liber 219, Pg. 653 | existing w/same |
| Records from | 10" Cedar N53°E 16.1' | to Pg. 660 | witnesses as above |
| Doyle Surveying | 10" Leaning Cedar | Delmer E. Porter | |
| & Engineering | S35°30'W 16.8' | LS#15410 | |
| | Stump of old Wit. in place | | |
| | N59°E 19' Stump | | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

| | |
|------------------|--------------------------|
| E-12 | |
| 4-7-94 | Fd. Conc. Mon. by Square |
| P. I. County | Cedar Post |
| State Remon. | N57°E 16.65' 13" Cedar |
| Norman J. Quaine | N19°E 20.64' 10" Cedar |
| #33984, Porter's | |
| Survey, P.C. | |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| |
|----------------------------------|
| E-12 |
| Conc. Mon. by Squared cedar post |
| N57E 16.65' 13" Cedar |
| N19°E 20.64' 10" Cedar |
| S09°W 12.78' 9" Maple |
| S34°E 20.12' 14" Cedar |

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmer E. Porter*
Date July 27, 1994

Signed by *Norman J. Quaine* Date Aug 17, 1994

Surveyor's Michigan License No. 33984