

State of Michigan Remonumentation Program
For Presque Isle County

PRESQUE ISLE COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 SEP -6 AM 10: 11

For corners **SURVEY &
REMONUMENTATION**
(County)

Located In: Corner Code #

Jane M. Lamb
REGISTER OF DEEDS

1. Public Land Survey APR 25 1995 T 36N R 2E E-13
COMMISSION T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

LIBER **311** PAGE **133**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman J. Quaine in a field survey on April 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-13

GLO Notes	Cedar 11" S85° E 64 Lks.	11-9-79	Found 2" Pipe
Resurvey 1856	Cedar 12" S30° W 9 Lks.	P.I. Co.	(No Witnesses)
January 1947	1" Pipe (16" down)	Local Remon.	Replaced cor. position
Records from	N30° W 25.65' 6" Balsam	Project	w/ 4" Conc. Mon. w/
Doyle Engineering	S35° W 30.70' 4" Tamarack	L.C.R.C. Pg.421	brass cap lettered
Fd. in Porter Survey		Delmer E. Porter	"P.I. Co Remon."
Records		LS#15410	N03° 13.08' 4" Aspen
			S38° W 22.70' 6" Balsam
			S08° W 14.44' 4" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13
4-7-94 Found 1" Pipe at old fence corner
Presque Isle Co, S40° W 15.28' 5" Cedar
State Remon. S87° W 16.82' 7" Cedar
Norman J. Quaine N01° E 27.08' 7" Cedar
#33984, Porter's 9' East to N-S Creek.
Survey, P.C.

Research indicates that corner placed in 1979 was set in error. Field search in April revealed that 4" concrete monument was under water in beaver pond and not available to remove as it is in an incorrect location and should not be used as the true location of E-13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13
1" Pipe at old fence corner
S40° W 15.28' 5" Cedar
S87° W 16.82' 7" Cedar
N01° E 27.08' 7" Cedar
N24° W 6.58' 3" Balsam

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Delmer E. Porter*
Date July 27, 1994

Signed by *Norman J. Quaine*

Date Aug. 17, 1994

Surveyor's Michigan License No. 33984