

1995 STATE OF MICHIGAN REMONUMENTATION PRESQUE ISLE COUNTY RECORDED

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

95 DEC 14 AM 10:29

2652

For corners in

Presque Isle Located In: (County)

Corner Code #

Janet M. Lamb  
REGISTER OF DEEDS

LIBER 316 PAGE 939

Register of Deeds Stamp & File Number

1. Public Land Survey	T	36N	R	2E	F7
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James A. Beck in a field survey on May 17, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F7	1856: Government Resurvey *by Geo. H. Cannon Set post and referenced: Y. Pine 15" S58°E 11 Links Y. Pine 16" N44°W 39 Links	Sept. 22, 1976: Corner recorded by Ronald Bischer, P.S. 22428.	Found 4" pipe. Raised with 1/2" rod and cap #15410. Referenced: N33°W 46.16 9" N. Pine S52°W 75.25 12" N. Pine N48°E 50.36 9" Oak
	Feb. 25, 1976: Corner recorded by Larry G. Beauregard, P.S. 18654.	Found grader blade 12" below road surface. Referenced: N35°W 45.75 12" Norway Pine S45°W 75.10 12" Norway Pine N45°E 49.75 10" Oak	Sept. 29, 1978: Corner recorded by Delmer E. Porter, P.S. 15410. Found 1/2" rod and cap. Set monument box. Referenced: N33°W 46.16 9" N. Pine S52°W 75.25 12" N. Pine N48°E 50.36 9" Oak


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F7 May 17, 1995:  
Remonumentation by  
James A. Beck,  
P.S. 21559.  
Ratified by Peer Group  
in accordance with P.A. 345  
Chairman Delmer E. Porter  
Date 11/21/95

Found 1/2" iron rod and cap (Delmer Porter, P.S. 15410) in monument box 2' North of blacktop road running East-West. Found all witnesses from last recording. Old witness tags grown over (measurements are to new tags)  
old: N33°W 46.08 14" N. Pine (set cap P.S. 21559)  
old: S52°W 75.26 14" N. Pine (set cap P.S. 21559)  
old: N48°E 50.36 12" Oak (set cap P.S. 21559)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F7 1/2" iron rod and cap (Delmer Porter, P.S. 15410) in monument box 2' North of blacktop road running East-West.  
Witnesses:  
old: N33°W 46.08 14" N. Pine (set cap P.S. 21559)  
old: S52°W 75.26 14" N. Pine (set cap P.S. 21559)  
old: N48°E 50.36 12" Oak (set cap P.S. 21559)  
new: S43°E 69.07 6" W. Pine (set cap P.S. 21559)



Signed by James A. Beck Date 11-28-1995  
Surveyor's Michigan License No. 21559