

State of Michigan Remonumentation Program  
For Presque Isle County.

PRESQUE ISLE COUNTY  
RECORDED

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

94 AUG 23 AM 10:11

For corners in

PRESQUE ISLE (County)	Located In:	Corner Code #
1. Public Land Survey	T 36N R 2E	F-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

*Jane M. Lamb*  
REGISTER OF DEEDS

LIBER 310 PAGE 932

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Ronald Bischer, in a field survey on April 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-13  
GLO Notes, Resurvey 1856 scribed on blaze  
Set Wood Post N40°E 34.82' 7" Oak  
Pine 12" N76°W 5 links S40°E 39.68' 6" Oak  
Pine 10" N56°E 5 links S20°W 24.33' 10" Oak

1974 - Delmar E. Porter Found 2" Pipe  
N05°E 4.00' 10" J. Pine  
found dead witness with NBT  
1978 - Delmar E. Porter Found 2" Pipe, replaced pipe with concrete monument with brass cap witness same as in 1974


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13  
Found concrete monument with brass cap lettered "Presque Isle County Remonumentation"  
S32°W 24.33' 12" Oak found foot blaze  
N40°E 34.82' 7" Oak found foot blaze  
S42°E 39.68' 8" Oak found foot blaze

SURVEY &  
REMONUMENTATION

SEP 09 1994

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13  
Presque Isle County Remonumentation Monument  
N46°E 35.24' 8" Oak  
S32°W 24.33' 12" Oak  
N40°E 34.82' 7" Oak  
S42°E 39.68' 8" Oak  
N32°W 65.10' 18" Oak

Ratified by Peer Group  
in accordance with P.A. 345

Chairman Delmar E. Porter  
Date July 27, 1994

\*Witness tags w/nails used.

Signed by Ronald R. Bischer Date July 20, 1994  
Surveyor's Michigan License No. 22428