

94 SEP 12 AM 10:41

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>36N</u> R <u>2E</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Janet M. Starns
 REGISTER OF DEEDS

LIBER **311** PAGE **250**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James A. Beck, in a field survey on March 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-7
 1856: Original monumentation in Government Resurvey. Set post at corner of Sections 15, 16, 21, and 22 and referenced:
 W Pine 28" N10°E 89 Links
 W Pine 15" S45°W 65 Links


1978: Delmer E. Porter, P.S. 15410, placed 1/2" rod and cap #15410 in monument box (from Corner Card furnished by Porter's Survey). Referenced:
 N46°W 61.45' 14" Jack Pine
 N41°E 48.44' 4" Balsam
 S49°E 74.38' 4" Apple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7
 1994: Found a 5/8" iron rod and cap P.S. 15410 (Delmer E. Porter) and two witnesses as documented by Delmer E. Porter (see above). Witnesses found (as recorded):
 N46°W 61.45' 14" Jack Pine
 N41°E 48.44' 4" Balsam

**Ratified by Peer Group
 in accordance with P.A. 345**

Chairman Delmer E. Porter
 Date August 29, 1994



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7
 1994: 5/8" iron rod and cap P.S. 15410 in centerline of blacktop road.
 Witnesses:
 N46°W (r) 61.45' (m) 61.38' 16" Dead Jack Pine (P.R., Tag 15410)
 N41°E (r) 48.44' (m) 48.56' 6" Balsam (P.R., tag 21559)
 South 34.68' Power Pole #HB31665 (tag 21559)
 S06°W 33.0' 1/2" iron and cap P.S. 21559
 S48°E 94.45' 4" White Pine (tag 21559)
 N02°E 43.99' S-most stem 6" Twin White Birch (tag 21559)
 P.R. = Previously Recorded

Signed by James A. Beck
 Surveyor's Michigan License No. 21559

Date August 25, 1994

2459