

RECORDED

94 SEP 12 AM 10:41

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| Presque Isle (County) | Located In: | Corner Code # |
|---------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | T <u>36N</u> R <u>2E</u> | <u>G-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

James M. Lamb
 REGISTER OF DEEDS

LIBER **311** PAGE **248**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, James A. Beck, in a field survey on June 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9
 1856: Original monumentation in Government Resurvey. Set post at corner of Sections 21, 22, 27 and 28 and referenced:
 W Pine 9" N30°W 33 Links
 B Ash 11" S55°E 39 Links

1975: Larry G. Beauregard, P.S. 18654, set DNR post and tab along side of 4" x 4" square stake and 2" pipe found at corner location. (From surveys recorded Feb. 25, 1976, L. 211, P. 764 & 765, Presque Isle County Records).
 Referenced:
 N60°E 40.23' 15" Cedar
 S60°E 21.40' 3" Cedar
 S05°W 28.54' 8" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9
 1994: Found 2" pipe in concrete and three witnesses as recorded by Ronald R. Bischer, P.S. 22428 (recorded March 9, 1984, Presque Isle County Records).
 Witnesses found (as recorded):
 S64°W 21.32' 4" Cedar
 S17°W 28.90' 8" Cedar
 S52°E 40.60' 12" Cedar

**Ratified by Peer Group
 in accordance with P.A. 345**
 Chairman Delmer E. Porter
 Date August 29, 1994



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9
 1994: 2" pipe in concrete.
 Witnesses:
 S64°W 21.32' 7" Cedar (P.R., tag 15410, Delmer E. Porter)
 S17°W 28.90' 10" Cedar (P.R., tag 15410, Delmer E. Porter)
 S52°E 40.60' 14" Cedar (P.R., tag 15410, Delmer E. Porter)
 S58°E 23.62' 4" Maple (set tag P.S. 21559)
 N50°E 2.00' Post with DNR tag (set tag P.S. 21559)

P. R. = Previously Recorded

Signed by James A. Beck Date August 25, 1994
 Surveyor's Michigan License No. 21559

2459