

JAN 17 1996  
1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION  
COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 316 PAGE 294

For corners in

Presque Isle  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 36N R 2E      H-1
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec.            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

PRESQUE ISLE COUNTY  
RECORDED

95 OCT 20 PM 4:28

*Jane M. Sumb*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Norman J. Quaine, in a field survey on April 2, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-1  
GLO Notes  
Resurvey 1856  
Cedar 14" N40°E 19½  
Aspen 13" N55°W 21  
Stream 0.83 chains east of 1/4 corner  
George H. Cannon

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1  
April 2, 1995  
Presque Isle County  
State Remonumentation  
Norman J. Quaine #33984  
Porter's Survey P.C.  
Fd. the creek called for in the GLO Notes  
Set 1/2" Rod & Cap #33984 by intersecting GLO Dist.  
From the creek C/L from the East and the line from  
the NW Twp. corner to the N 1/4 of Sec. 1  
The corner's position fit the GLO calls for the  
creek to the west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1  
Left 1/2" Rod & Cap #33984  
S51°E 31.90' 12" Cedar  
S06°W 14.47' 12" Cedar  
S53°W 5.55' 12" Twin Cedar  
N51°E 4.68' 16" Cedar  
East 54.8' C/L Creek  
North 12' E'y edge creek

Ratified by Peer Group  
in accordance with P.A. 345

Chairman *[Signature]*

Date 9/20/95

\*Witness tags & nails used.

Signed by Norman J. Quaine  
Surveyor's Michigan License No. 33984

Date October 19, 1995