

JAN 17 1996
1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 316 PAGE 295

PRESQUE ISLE COUNTY
REGISTERED

95 OCT 20 PH 4: 28

June M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

2012
For corners in
Presque Isle
(County)

Located In:	Corner Code ##
T 36N R 2E	I-1
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman J. Quaine, in a field survey on April 7, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1
GLO Notes
Resurvey 1856
Tamarack 8" N48°W 27
W. Pine 11" N20°E 8½
Tamarack 7" North 0.97'
George H. Cannon

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1
April 7, 1995
Presque Isle County
State Remonumentation
Norman J. Quaine #33984
Porter's Survey P.C.
Fd. no evidence of corner's position
Set 1/2" Rod & Cap #33984
By single proportion

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1
Left 1/2" Rod & Cap #33984
N50° E 16.73' 9" Cedar
N83° E 5.31' 6" Cedar
S15° W 34.62' 8" Maple
S73° W 27.30' 10" Cedar

Ratified by Peer Group
in accordance with P.A. 345
Chairman Delores E. Porter
Date 9/20/95

*witness tags & nails used.

Signed by Norman J. Quaine Date OCTOBER 19, 1995
Surveyor's Michigan License No. 33984