

SURVEY &
REMONUMENTATION

1995 ~~PRESQUE ISLE~~ ^{JAN 17 1995} PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

2207

COMMISSION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **316** PAGE **310**

For corners in

<u>PRESQUE ISLE</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>36N</u> R <u>2E</u>	<u>I-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

PRESQUE ISLE COUNTY
(RECORDED)

95 OCT 20 PM 4:33

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Ronald Bischer, in a field survey on March 3, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes - 1856 Resurvey
Geo H. Cannon
Set wood post
Tamarack 11" S40°E 20 lks
Tamarack 10" N41°W 7 lks

No record of subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set 1/2" Rod and Cap #22428 by single proportion.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" Rod and Cap #22428
S80°W 12.10' 14" Cedar
N25°W 23.96' 14" Cedar
N38°E 36.88' 4" Red Maple
S26°E 29.53' 8" Cedar

Nails with witness tag #22428 used.

Ratified by Peer Group
in accordance with P.A. 345

Chairman *[Signature]*

Date 9/20/95

Signed by Ronald R. Bischer

Date Oct. 3, 1995

Surveyor's Michigan License No. 22428