

SURVEY & RE-MONUMENTATION

1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION
 JAN 17 1996

2229

COMMISSION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **316** PAGE **312**

For corners in

| <u>PRESQUE ISLE</u> (County) | Located In: | Corner Code :# |
|------------------------------------|--------------------------|----------------|
| 1. Public Land Survey | T <u>36N</u> R <u>2E</u> | <u>I-6</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

PRESQUE ISLE COUNTY
 RECORDED

95 OCT 20 PM 4:34

Janet M. Lamb
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Ronald Bischer, in a field survey on March 3, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GL0 Notes - 1856 Resurvey S59°E 27.64' 9" Balsam
 Geo. H. Cannon
 Set wood post 05-24-77 - Delmar E. Porter
 Tamarack 6" S80 E 14 lks ½" Rod & RLS Cap - witness same as 05-19-77
 Tamarack 8" N54 W 24 lks (Bischer)
 05-19-77 - Ronald R. Bischer 11-06-78 - Delmar E. Porter
 Set ½" Rod by single proportion Replaced ½" Rod with concrete monument
 S88°W 41.20' 10" Balsam with brass cap
 N65°E 32.19' 5" Aspen witnesses same as 05-19-77 (Bischer)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Presque Isle County Remonumentation Monument
 (concrete monument with brass cap)
 N65°E 32.19' 6" Aspen
 S88°W 41.20' 10" Balsam - blown over
 S59°E 27.64' 9" Balsam - blown over



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Presque Isle County Remonumentation Monument
 N65°E 32.19' 6" Aspen
 S18°E 61.48' 9" Balsam
 S10°W 53.35' 4" Black Ash
 N62°W 50.13' 5" Balsam

Ratified by Peer Group
 in accordance with P.A. 345

Chairman *Delmar E. Porter*
 Date 9/20/95

Nails with witness tag #22428 used.

Signed by Ronald R. Bischer Date Oct 3, 1995
 Surveyor's Michigan License No. 22428